


## **Drip Feed Settings in PC DNC Editor**

Go to I/O Menu Configure I/O Device Select Machine Click on Advanced Check Handshake using device driver Click OK



If you are using a <u>NATIVE COM Port</u> (DB9 port on back of computer) do the following (not applicable with BTR):

In Windows Device Manager Open Ports (COM and LPT) Right Click on native Com Port (COM 1) Click Properties Port Settings Click Advanced button

> Suburban Machinery Software, Inc. 37777 Harlow Drive, Willoughby Ohio 44094 (440) 951-8974 subsoft@buckeyeweb.com




Check "Use Fifo buffers"

Make sure Receive is all the way to right (High)

Make sure Transmit is set all the way to left (low)

(If you are using a USB adapter, please call. The settings here will be different.

If still not successful, try the following settings.



Suburban Machinery Software, Inc. 37777 Harlow Drive, Willoughby Ohio 44094 (440) 951-8974 subsoft@buckeyeweb.com